

MONROE COUNTY HEALTH CENTER

MADISONVILLE, TENNESSEE



ARCHITECTS
WEEKS
AMBROSE
MCDONALD
INC.



Main Entry



Dental Suite

The check-in stations are equipped with sound panels and all exam rooms have sound attenuation blankets in the walls. The center core has a higher roof that allowed higher ceilings in larger spaces including the main waiting room, work area and conference room. With its separate entry, the conference room can also double as a community meeting space. The building is also designed to accommodate future expansion.



Monroe County Health Center

The building design incorporates special features to accommodate recent HIPPA guidelines for health departments as it relates to patient privacy.

A pavilion formerly occupied the site at the top of a hill. It had been used for community events and as a meeting place for a local Native American tribe. The main entry porte cohere was designed to recall the former wooden pavilion structure. The remaining structure is a steel frame and steel stud building with stucco and brick veneer. This made for an economical building envelope. The 13,076 sf health center was completed in 2006 at a total construction cost of \$1,608,000 or \$123/sf.

The building is designed around a central administrative core with patient areas, separated into adult and children's areas, spread around the perimeter. Additional spaces include outreach spaces for private patient conferences with separate entry, staff conference, offices and break room. With a separate entry is a dental suite with multiple exam rooms and a radiology station. This space was finished out under a separate contract using designated funding specifically for this unique and expanded dental program. The building design incorporates special features to accommodate recent HIPPA guidelines for health departments as it relates to patient privacy.



Waiting Area



Dental Examination Room



Conference Room