

PIGEON FORGE ELEMENTARY SCHOOL

SEVIER COUNTY SCHOOLS



ARCHITECTS
WEEKS
AMBROSE
MCDONALD
INC.



View Looking Northwest

AWAM was retained for the design of a new elementary school in Pigeon Forge, Tennessee. The school building is organized in a very simple and straight forward configuration. The central core was designed to accommodate the ultimate 750 pupil population, flanked on either side by exterior classrooms for 600 pupils. The original 53,091 sf school was finished in 1985 for the 600 student capacity. To reach their goal for 750 students, six additional classrooms were added in 1990 and 1994. The building structure is steel frame supporting precast cementitious roof deck and rigid insulation with standing seam metal roofing. In 1985, the project cost was \$2,118,286, or \$40/sf. The equivalent construction cost for 2016 is estimated at \$7,963,650, or \$150/sf.



Main Entry

www.awaminc.com



Entry Lobby



Classroom



Front Facade

The 600 pupil elementary school building is organized in a very simple and straight forward configuration with the central core, which is designed to accommodate the ultimate 750 pupil population